




Virginia Graeme Baker Pool and Spa Safety Act of 2007
Drain Cover Comparison

Does your drain cover look like one of these?



The above covers are **NOT** ASME/ANSI A112.19.8-2007 approved.

How will I know if the drain cover I have is compliant?

The cover will have the following embossed or permanently marked in a location that is visible when installed:

- (1) ASME/ANSI A112.19.8-2007 or ASME/ANSI A112.19.8a-2008 certification
- (2) "For Single or Multiple Drain Use", "For Single Drain Use", or "For Multiple Drain Use Only".
- (3) Maximum flow rate in gallons per minute (gpm)
- (4) "Wall Only", "Floor Only", or "Wall and Floor" installations
- (5) Cover life (Example: 3 years)
- (6) Manufacturer name or registered trademark
- (7) Model designation

We offer an assortment of anti-entrapment covers that meet the new standards.

To locate a store near you, call 1-800-LESLIES (800-537-5437).

The law requires **ANSI/ASME A112.19.8-2007 approved drain covers** (all public pools and spas) and a ***Safety Vacuum Release System (SVRS)** for all public swimming pools and spas with single main drains that can be blocked. The drain sump must also meet the specific requirements of the act. As noted in the complete act, the **compliance date** for all pools and spas to meet the requirements is **December 19, 2008**. For more information, please visit www.cpssc.gov

Note: The pool or spa must comply with state and local entrapment prevention requirements. Verify that compliance with the federal law does not conflict with local health codes or regulations. *Other options available.